

INDIAN INSTITUTE OF MANAGEMENT BODH GAYA					
Construction of a floor of a standard Basket ball Ground inside Hostel Campus of IIM BODH GAYA					
SL. NO.	DESCRIPTION OF WORK	QTY.	UNIT	RATE(RS.)	AMOUNT(RS.)
1	Earth work in excavation of foundation trenches or drains in all sorts of soil (including mixed soil, but excluding laterite or sandstone) including removing, spreading or stacking the spils within a lead of 75 mm as directed. (A) Depth of excavation not exceeding 1500 mm	280.00	Cu.M.		
2	Filling in foundation or plinth by silver sand in layers not exceeding 150 mm. as directed and consolidating same by thorough saturation with water raming complete including the cost of supply of sand.	168.30	Cu.M.		
3	Single brick flat soiling of picked jhama bricks including rammng and dressing bed to proper level and filling joints with powdered earth or local sand.	561.00	Sqm.		
4	Plain Cement concrete with graded stone chips (excluding shuttering) in ground floor and foundation (1:3:6).	42.08	Cu.M.		
5	Hire and labour charges for shuttering with centreing and necessary staging upto 4 m. using approved stout props and thick hard wood planks of approved thickness with required branching for concrete slabs, beams, m columns, lintels curved or straight including fitting, fixing and stricking out after completion of works. . 25 mm. to 30 mm. thick wooden shuttering as per decision & direction of Engineer-in-Charge.	17.50	Sqm.		
6	Reinforcement for reinforced concrete work in the all sorts structures including distribution bars, stirrups, bainders, etc. including supply of rods, initial straightening and removal of loose rust (if necessary), For work in foundation, basement and upto roof of ground floor/upto 4m. Tor steel/Mild steel.	2.24	M.T.		
7	Ordinary cement concrete (mix 3:1.5:1)M-20 with graded stone chips (20 mm. down excluding shuttering and reinforcement, if any, in ground floor as per IS 456-2000).	56.10	Cu.M.		
				Total =	

Date:

Name of the Bidder

Signature with official seal